BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work: Improvements Road and Drain at Kogilu layout in Ward No. 05

Agency:-m/s KRIDL

SCHEDULE-B

Sl No	App Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
1	104	KSRRB 300-1. **Earthwork excavation** by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete asper specifications.MORTH / Chapter 3(I No-19.1, P No-133)	Cum	180.4812	Rupees One Hundred Eighty And Paise Forty Eight Only
2	482.63	KSRB 4-1.2 : Providing and laying in position **plain cement concrete of mix 1:3:6** with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms^thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No. KBS 4.1, 4.2.(P.No-12,I No-4.2)	Cum	5937.1236	Rupees Five Thousand Nine Hundred Thirty Seven And Paise Twelve Only
3	28.35	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of **design mix M20** with OPC cement @ 320kgs, with 20mmand down size graded granite metal coarse aggregates @0.0.69cum and fine aggregtes @ 0.460cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6(I No-4.11,P No-13)	Cum	7072.5426	Rupees Seven Thousand Seventy Two And Paise Fifty Four Only
4	216.00	KSRB 4-6.4 : Providing and **removing centering, shuttering,** strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2	Sqm	344.7438	Rupees Three Hundred Forty Four And Paise Seventy Four Only

(Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

App Qty	Description of work	Approved Rates of m/s KRIDL		
		Unit	Rate in Figures	Rate in Words
1.70	KSRB 4.9.2 : Providing **T.M.T steel reinforcement** for R.C.C workincluding straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire andanchoring to the adjoining members wherever necessary complete asper design (laps, hooks and wastage shall not be measured and paid)cost of materials, labour, HOM of machinery complete as perspecifications.Specification No. KBS 4.6.3(I No-4.46.2,P No-17)	Tn	71310.196	Rupees Seventy One Thousand Three Hundred Ten And Paise Twenty Only
6 81.00	Providing and Fixing **pre cast covering Slab** made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)	Sqm	2100	Rupees Two Thousand One Hundred Only
7 624.60	KSRRB M300-14. **Excavation for roadwork** in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location to a lead of 1km and complete as per specifications. MORTH Specification No.301(P.No. 143, I.No. 19.14)	Cum	138.1236	Rupees One Hundred Thirty Eight And Paise Twelve Only
8 468.45	KSRB 4-1.5 : Providing and laying in position plain **cement concrete of mix M20** with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No. 4.5 of PWD SR 2015-16)	Cum	6520.7172	Rupees Six Thousand Five Hundred Twenty And Paise Seventy Two Only
9 3123.00	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.(P.No.177, I.No. 22.7)	Sqm	105.894	Rupees One Hundred Five And Paise Eighty Nine Only

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Executive Engineer
Project Division
Yelahanka Zone

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Contractor

App Qty	Description of work	Approved Rates of m/s KRIDL		
		Unit	Rate in Figures	Rate in Words
500	Providing **groove cutting** for width of 5mm to 10mm and depth 80mm- 100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade,coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. - for concrete pavement (P.No.177, I.No. 22.7)	mtr	135.309	Rupees One Hundred Thirty Five And Paise Thirty One Only
3554.9	KSRRB 500-3. **Scarifying existing stone metal layer** upto 75mm thick along with their bituminous surface, picking up scarified materials and stacking of old serviceable materials with lead of 100 m. sequential spreading of the salvaged aggregates with fresh aggregates on prepared base and consolidating as per water bound macadam specifications including cost of all labour, HOM of machineries complete as per specifications. MORTH specification clause 501 (P.No. 161, I.No. 21.30)	Sqm	102.3642	Rupees One Hundred Two And Paise Thirty Six Only
799.85	KSRRB M400-17 : Providing, laying, spreading and compacting graded stone aggregate to **wet mix macadam** specification including premixing the material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.(P.No.158, I.No. 20.18)	Sqm	1962.5688	Rupees One Thousand Nine Hundred Sixty Two And Paise Fifty Seven Only

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

3/18

Executive Engineer
Project Division
Yelahanka Zone

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Contractor